



Power Modulator 3 has 4 contactors, each one can take up to 300 VAC, 30 Amp. SCPM can operate up to 4 zones with selectable sequencing method. SCPM has double wire terminals for the load connections. The built-in ground fault protection must be disabled, by disconnecting the two wires connected to the green terminals on the Ground Fault Sensor.